www.delumber.com

PROLINES

February 2009 — The Newsletter for the Professional Builder

LVL Scaffold Planks

The **Occupational Health and Safety Code** of the Province of Alberta contains the following requirement of employers regarding the use of commercially manufactured Scaffold Planks.

Scaffold planks
329(1) An employer must ensure that a commercially manufactured scaffold plank is used, stored, inspected and maintained according to the manufacturers specifications.

LP LVL is a vast improvement over solid wood scaffold Planks. Researched over a 10 year period and thousands of jobsites across the country, this Laminated Veneer product is reliable and safe and has stood the test of time. Defects such as knots, irregular grain and splits, which would weaken solid lumber planks, are dispersed during the veneer peeling process, and are then graded and laid in a specific pattern so the naturally occurring defects have no concentrated effect on the scaffold plank. While some grades of solid wood scaffold planks may be initially less expensive, the shorter life span plus the cost to rod and pin the solid lumber planks may offset the initial cost savings.

We keep the 1 1/2" x 9 1/4" x 16' in stock. To ensure the safety of you and your workers, and extend the life of your new LP Scaffold Planks please follow the Span Chart and the information regarding storage, and jobsite instructions. Ask your Davidson Enman Lumber Ltd. sales representative for more information, or to arrange a delivery to your jobsite.

Simple Span	
Loading Condition	1 1/2" x 9 1/4"
50 PSF	10'- 6"
75PSF	9'- 0"
1 Person	10'- 6"
2 Person	8' - 0"
3 Person	6' - 0"

Two Equal Spans	
Loading Condition	1 1/2" x 9 1/4"
50 PSF	11'- 0"
75 PSF	9'- 6"
1 Person	12'- 0"
2 Person	8'- 6"
3 Person	6'- 6"

PSF– pounds per Square Foot

We will be closed Monday, February 16, 2009 for Family Day